

Permit Application Package (Compiled) (Mock)

P4.2 compiled package | Application: EL-2026-01472 (mock)

EV Charging Site Project — Phase 4 Outputs (MOCK)

This compiled PDF represents the complete permit submission package as uploaded to the AHJ portal: forms + stamped drawings + supporting attachments + submission receipt.

Package sections (mock):

- P4.2_AHJ_ApplicationForms_2026-01-29.pdf
- P4.1_PermitSet_Stamped_2026-01-29.pdf
- P4.SupportingAttachments_Electrical_2026-01-29.pdf
- P4.SubmissionReceipt_AHJ_Confirmation_2026-01-29.pdf

MOCK / EXAMPLE ONLY

AHJ Permit Application Forms (Mock)

P4.2 forms export | Date: 2026-01-29

EV Charging Site Project — Phase 4 Outputs (MOCK)

Application info (mock)

AHJ:	City of Palo Alto — Building Division (Electrical Permits)
Permit application number:	EL-2026-01472 (mock)
Site address:	Place (Palo Alto, CA) (mock)
Project description:	Install (8) Level-2 EVSE with load management (mock)
Applicant:	Jordan Lee (PM) (mock)
Contractor:	Romero Electric (mock)

Attachments declared (mock):

- Stamped drawings (P4.1)
- Load calc summary (P2.1)
- EVSE cut sheet (P1)
- EMS brief (P2)

MOCK / EXAMPLE ONLY

Stamped Permit Drawings (Mock)

P4.1 | Stamp date: 2026-01-29 | Engineer-of-Record: Priya Shah, PE (mock)
EV Charging Site Project — Phase 4 Outputs (MOCK)

STAMP BLOCK (mock)

Priya Shah, PE (mock)
CA PE ##### (mock)
Date: 2026-01-29

This cover page is added to represent an EOR stamped set. The remainder of the set is the compiled P3.6 unstamped permit set (mock).

NOTE: This is not a real stamp. For mock documentation only.

MOCK / EXAMPLE ONLY

Permit Drawing Set — Unstamped (Compiled) (Mock)

P3.6

EV Charging Site Project — Phase 3 Outputs (MOCK)

This file represents the compiled unstamped electrical permit drawing set assembled from P3.1–P3.5. In a real project this compilation is performed under document control with sheet indexing and QA logs.

Included sheets (mock):

- P3.1_OneLine_Prelim_Unstamped_2026-01-26.pdf
- P3.2_SitePlan_EVSE_Locations_Prelim_2026-01-26.pdf
- P3.3_Conduit_Trenching_Details_ElectricalImpacting_2026-01-26.pdf
- P3.4_PanelSchedules_Updated_MDP_and_EVSP_2026-01-26.pdf
- P3.5_ElectricalNotes_CodeSheets_2026-01-26.pdf


MOCK / EXAMPLE ONLY

NOTE: This compilation is a mock artifact; replace with real CAD/PDF exports and stamps.

E-001 — One-Line Diagram (Preliminary, Unstamped) (Mock)

P3.1
EV Charging Site Project — Phase 3 Outputs (MOCK)

ONE-LINE DIAGRAM (mock)



NOTES (mock):


- Existing service basis: 800A, 208Y/120V, 3Ø (verify in Phase 1 evidence).
- EVSE loads treated as continuous; branch OCPD basis 40A per 32A continuous (mock).
- EMS/load management shown to cap aggregate EV demand to $\leq 250A$ (mock basis).
- Final conductor sizing, AIC, and coordination to be confirmed in stamped set.

PROJECT (mock): EV Charging Site Project	SHEET: E-001	ISSUED FOR:
SHEET TITLE: One-Line Diagram (Preliminary)	REV: 0	UNSTAMPED
ADDRESS: Place (Palo Alto, CA) (mock)	DATE: 2026-01-26	(electrical-only)

E-002 — Site Plan with EVSE Locations (Preliminary) (Mock)

P3.2
EV Charging Site Project — Phase 3 Outputs (MOCK)

GARAGE PLAN — EVSE LOCATION OVERLAY (mock)



PROJECT (mock): EV Charging Site Project	SHEET: E-002	ISSUED FOR:
SHEET TITLE: Site Plan — EVSE Locations	REV: 0	UNSTAMPED
ADDRESS: Place (Palo Alto, CA) (mock)	DATE: 2026-01-26	(electrical-only)

E-003 — Conduit & Trenching Details (Electrical-Impacting) (Mock)

P3.3
EV Charging Site Project — Phase 3 Outputs (MOCK)

This sheet documents electrical-impacting routing assumptions, transition points, and typical details. It is not a civil/constructability plan.

DETAIL 1 — Feeder Path (mock)

MDP → EVSP-1 assumed path length: 165 ft (basis)

DETAIL 2 — Typical Raceway Notes (mock)

- Raceway sized per NEC/CEC Chapter 9 (mock).

- Parallel conductors permitted as designed (mock).

- Provide EGC with feeder conductors.

- Maintain separation from comms wiring (as applicable).

DETAIL 3 — EVSE Branch Typical (mock)

- Branch: 40A OCPD for 32A continuous (mock basis).

- Conductor sizing per terminal temp rating + derating.

- Provide disconnecting means as required by code/AHJ.

- Label EVSE circuit ID at equipment and panel.

DETAIL 4 — Grounding/Bonding Intent (mock)

- Bond raceways where required (mock).

- EGC sized per code basis (final by EOR).

- Panel ground bars bonded to GES (reference).

- Provide bonding jumpers at transitions.

<div>PROJECT (mock): EV Charging Site Project</div> <div>SHEET TITLE: Conduit & Trenching Details (Electrical-</div> <div>ADDRESS: Place (Palo Alto, CA) (mock)</div>	<div>SHEET: E-003</div> <div>REV: 0</div> <div>DATE: 2026-01-26</div>	<div>ISSUED FOR:</div> <div>UNSTAMPED</div> <div>(electrical-only)</div>
---	---	--

File: P3.3_Conduit_Trenching_Details_ElectricalImpacting_2026-01-26.pdf | Generated: 2026-01-22 | Page 1

E-004 — Updated Panel Schedules (MDP + EVSP-1) (Mock)

P3.4
EV Charging Site Project — Phase 3 Outputs (MOCK)

MDP — Updated (excerpt) (mock)

Slot	Breaker	Load	Notes
40/42/44	350A 3P	EVSP-1 feeder	Managed to 250A (mock)
17	200A 3P	SUBP-1	Existing
57	Spare	Spare/Space	Available 3-pole

EVSP-1 — New (excerpt) (mock)

Slot	Breaker	Load	Notes
1	40A 3P	EVSE-01	32A cont (mock)
2	40A 3P	EVSE-02	32A cont (mock)
3	40A 3P	EVSE-03	32A cont (mock)
4	40A 3P	EVSE-04	32A cont (mock)
5	40A 3P	EVSE-05	32A cont (mock)
6	40A 3P	EVSE-06	32A cont (mock)
7	40A 3P	EVSE-07	32A cont (mock)
8	40A 3P	EVSE-08	32A cont (mock)

NOTE: schedules are mock excerpts; full schedules included per P1 evidence in real project.

PROJECT (mock): EV Charging Site Project	SHEET: E-004	ISSUED FOR:
SHEET TITLE: Panel Schedules (MDP + EVSP-1)	REV: 0	UNSTAMPED
ADDRESS: Place (Palo Alto, CA) (mock)	DATE: 2026-01-26	(electrical-only)



E-005 — Electrical Notes & Code Sheet (Mock)

P3.5
EV Charging Site Project — Phase 3 Outputs (MOCK)

GENERAL NOTES (electrical-only, mock)

- 1. Applicable code basis: 2022 California Electrical Code (CEC) (mock). Verify AHJ amendments.
- 2. EVSE loads treated as continuous; size OCPD and conductors accordingly (125% basis).
- 3. EMS/load management (if used) shall be listed and configured to enforce aggregate cap (mock: 250A).
- 4. Provide identification labeling for EV equipment and circuits; coordinate with panel schedules.
- 5. Provide grounding and bonding per code; bond raceways as required.
- 6. Verify available fault current and minimum AIC ratings in final stamped set.

SYMBOLS / LEGEND (mock)

-  EVSE location marker
-  EMS / Load management annotation

PROJECT (mock): EV Charging Site Project	SHEET: E-005	ISSUED FOR:
SHEET TITLE: Electrical Notes & Code Sheet	REV: 0	UNSTAMPED
ADDRESS: Place (Palo Alto, CA) (mock)	DATE: 2026-01-26	(electrical-only)

Supporting Attachments — Electrical (Mock)

P4 supporting bundle | Date: 2026-01-29

EV Charging Site Project — Phase 4 Outputs (MOCK)

This file represents a compiled bundle of common electrical supporting attachments included with an AHJ permit submission (mock). It references Phase 1 and Phase 2 evidence pointers.

Included (mock):

- P2/Outputs/P2.1_LoadCalc_Summary_2026-01-22.pdf
- P2/Outputs/P2.2_Architecture_Decision_Record_2026-01-22.pdf
- P1/Inputs/P1-I04_EVSE_CutSheet_ElectriCharge_L2-7.6-G_revA.pdf
- P2/Inputs/P2-W04_EMS_TechnicalBrief_revB_2026-01-21.pdf
- P1/Inputs/P1-I05_AHJ_Electrical_Permitting_CodeBasis_2026-01-17.pdf

MOCK / EXAMPLE ONLY

P2.1 Load Calculation Summary (Mock)

Prepared: 2026-01-22 (v1.0) | Basis: Phase 1 evidence pointers (mock)
EV Charging Site Project — Phase 2 Outputs (MOCK)

This summary captures the key results of the Phase 2 load calculation. Replace with an Engineer-of-Record signed calculation and jurisdiction-specific methodology where required.

Inputs (by evidence pointer, mock):

- Panel schedules: P1/Inputs/P1-I02_PanelSchedules_MDP_and_Subpanels_2026-01-16.pdf
- EVSE cut sheet: P1/Inputs/P1-I04_EVSE_CutSheet_ElectriCharge_L2-7.6-G_revA.pdf
- AHJ/code basis: P1/Inputs/P1-I05_AHJ_Electrical_Permitting_CodeBasis_2026-01-17.pdf
- EMS brief: P2/Inputs/P2-W04_EMS_TechnicalBrief_revB_2026-01-21.pdf

Key calculation results (mock):

Parameter	Value
Ports	8
EVSE continuous current / port	32A
Continuous factor	125%
Design current / port	40A
Total unmanaged EV current	320A
Headroom basis (screening)	250A
Result	Unmanaged exceeds headroom by 70A → EMS required

NOTE: Mock summary only; final engineering must be stamped where required.

P2.2 Architecture Decision Record (Mock)

Prepared: 2026-01-22 (v1.0) | Decision: Managed-load architecture
EV Charging Site Project — Phase 2 Outputs (MOCK)

This record documents the selected EV electrical architecture based on the Phase 2 load calculation and Phase 1 site constraints. Replace with an Engineer-of-Record signed decision where required.

Decision drivers (mock):

- Project constraint: avoid service upgrade unless unavoidable.
- Unmanaged EV load (320A) exceeds headroom basis (250A).
- Maintain 8-port scope without reducing EVSE count.
- Adopt listed EMS/load management to cap aggregate EV demand.

Selected architecture (mock):

- New EV subpanel: EVSP-1, 400A bus (mock).
- Feeder OCPD: 350A, 3-pole (mock).
- Branch circuits: (8) 40A OCPD for EVSE-01..EVSE-08 (mock).
- EMS: cap aggregate EV demand to $\leq 250A$ (setpoint documented on drawings).

Downstream impacts (mock):

- P3.1 one-line must depict EMS and cap logic; include fail-safe note placeholder.
- P3.4 schedules must reflect EVSP-1 and branch circuit IDs.
- P6 utility package should include EMS brief and cap statement.

NOTE: Mock decision record; replace with signed EOR memo and attachments.

EVSE Cut Sheet (Mock) — ElectriCharge L2-7.6-G (revA)

Installer/Vendor PDF (mock format) | Rev: A
EV Charging Site Project — Phase 1 Inputs (MOCK)

Key Electrical Ratings (mock)

Supply system:	208Y/120V, 3-phase (line-to-line load) (mock)
Nominal output power:	7.6 kW (nominal)
Continuous current:	32A
Recommended OCPD:	40A
Enclosure:	NEMA 3R (mock)
Communications:	OCPP 1.6J (mock)
Listing:	UL 2594 / UL 2231 (mock)

Installation Notes (mock)

Branch circuit sizing shall comply with applicable NEC/CEC requirements for continuous loads. A 40A breaker is typical for 32A continuous output. Final breaker and conductor sizing per Engineer-of-Record.

EVSE Cut Sheet (Mock) — Wiring/Dimensions (revA)

ElectriCharge — Product Data Sheet (mock)
EV Charging Site Project — Phase 1 Inputs (MOCK)

Wiring (mock excerpt)

Input: L1, L2, L3, G (no neutral required). Optional control wiring per network kit (mock).

(Mock wiring diagram placeholder)

Dimensions (mock)

- Height: 18.5 in
- Width: 12.0 in
- Depth: 6.0 in
- Mounting: wall or pedestal (mock accessory)

NOTE: Generated mock cut sheet for documentation format realism only.

EVSE Cut Sheet (Mock) — Labeling / Installation Checklist (revA)

Field-install notes (mock)

EV Charging Site Project — Phase 1 Inputs (MOCK)

This page summarizes common electrical-only installation considerations typically included in manufacturer documentation or installer checklists. Final requirements must follow the AHJ-adopted code basis and the EOR permit set.

Labeling / placarding (mock):

- Circuit identification label at EVSE and at panel schedule.
- If an EMS/load management system is used, label the controlled system and setpoint.
- Mark EVSE as continuous load; confirm breaker sizing basis (125%).

Electrical notes (mock):

- No neutral required for line-to-line EVSE supply (if configured as such).
- Provide equipment grounding conductor with branch circuit conductors.
- Verify maximum OCPD per manufacturer listing.
- Final conductor sizing per terminal temperature ratings and derating factors.

NOTE: This checklist is illustrative for mock documentation realism.

EMS Technical Brief (revB) — Load Management for EVSE (Mock)

Vendor brief (mock) | Rev: B | Date: 2026-01-21
EV Charging Site Project — Phase 2 Inputs (MOCK)

This document is a mock technical brief for a listed Energy Management System (EMS) used to cap aggregate EV charging demand. Replace with actual vendor documentation and listing evidence.

Key capabilities (mock):

- Aggregate current cap setpoint (mock): 250A at EV feeder.
- Per-port load allocation across up to 16 ports (mock).
- Fail-safe behavior: on comms loss, enforce conservative cap (mock).
- Listed to applicable standards (mock listing placeholders).
- Provides configuration export for as-built documentation (Phase 7).

Integration points (mock):

- Measures feeder current via CTs at EVSP-1 feeder (monitoring point).
- Controls EVSE output via network interface (OCPP) or hardwired control (mock).
- Setpoint documented on one-line and notes sheet (Phase 3).

EMS Technical Brief (revB) — Configuration + Compliance Notes (Mock)

Appendix: configuration fields (mock)
EV Charging Site Project — Phase 2 Inputs (MOCK)

Configuration fields (mock):

Project ID:	EV-PA-001 (mock)
Cap setpoint:	250A
Monitoring point:	EV feeder at MDP/EVSP-1
Fail-safe mode:	Cap enforced on fault
Export format:	PDF + JSON (mock)

MOCK / EXAMPLE ONLY

NOTE: This is a generated mock EMS brief for documentation realism only.

AHJ Electrical Permitting + Code Basis Evidence Capture (Mock)

Capture date: 2026-01-17 | Source: AHJ website (mock capture)
EV Charging Site Project — Phase 1 Inputs (MOCK)

This PDF represents a mock evidence capture of the Authority Having Jurisdiction (AHJ) electrical permitting page and adopted code basis. Replace with an actual screenshot/capture and preserve metadata.

City of Palo Alto — Building Division (Electrical Permits) (mock)

<https://www.cityofpaloalto.example/building/electrical-permits> (mock)

AHJ (electrical permitting):	City of Palo Alto — Building Division (Electrical Permits)
Adopted electrical code:	2022 California Electrical Code (CEC) (mock)
Amendments noted:	Local amendments may apply (mock note)
Permit submittal method:	Online portal upload (mock)
Plan check contact:	electricalpermits@paloalto.example (mock)

Metadata: captured_by=Jordan Lee (mock) | method=PDF print | timezone=PT | browser=Chrome (mock)

AHJ Electrical Permitting — Submittal Requirements Excerpt (Mock)

Source: AHJ checklist page (mock capture)

EV Charging Site Project — Phase 1 Inputs (MOCK)

This page captures a mock summary of common AHJ electrical submittal requirements, preserved as evidence for Phase 1 intake and Phase 4 application packaging.

Requirements checklist (mock):

- Stamped electrical plans (PDF) with title blocks and sheet index.
- Load calculation summary (where applicable).
- Equipment cut sheets (EVSE + EMS if used).
- Site/address and applicant/contractor information.
- Single-line / one-line diagram included in plan set.

Code adoption excerpt (mock):

The City has adopted the 2022 California Electrical Code (CEC). Project documents shall reference the adopted code edition and any local amendments as applicable. (Mock excerpt.)

MOCK / EXAMPLE ONLY

AHJ Submission Receipt / Confirmation (Mock)

Portal confirmation export | Date: 2026-01-29
EV Charging Site Project — Phase 4 Outputs (MOCK)

AHJ:	City of Palo Alto — Building Division (Electrical Permits)
Application number:	EL-2026-01472 (mock)
Submission method:	Online portal upload (mock)
Submitted by:	Jordan Lee (PM) (mock)
Submission date/time:	2026-01-29 14:18 PT (mock)
Status:	Submitted (mock)

MOCK / EXAMPLE ONLY

NOTE: Mock receipt; replace with actual portal download/screenshot PDF.