

# Utility Rework Package (Mock)

P6.3 | Date: 2026-02-27 | Addresses utility deficiency (mock)

EV Charging Site Project — Phase 6 Outputs (MOCK)

This compiled package responds to the utility's deficiency notice by providing an EMS clarification memo (monitoring point + cap + fail-safe) and re-attaching key engineering evidence.

## Included sections (mock):

- 1) Utility deficiency notice (reference)
- 2) EMS clarification memo (monitoring point + fail-safe cap)
- 3) Phase 2 load calc summary + architecture decision record
- 4) EMS technical brief + EVSE cut sheet (design basis)
- 5) Stamped permit set (reference, if requested by utility)

MOCK / EXAMPLE ONLY

# EMS Clarification Memo (Mock)

Monitoring point + cap setpoint + fail-safe behavior  
EV Charging Site Project — Phase 6 Outputs (MOCK)

This memo clarifies how the EMS enforces the aggregate cap to satisfy utility review. Replace with vendor/EOR letter as required.

## Clarifications (mock):

- Monitoring point: EV feeder current measured at EVSP-1 feeder via CTs (mock).
- Setpoint: aggregate cap configured to 250A maximum (mock).
- Fail-safe: on comms loss/fault, cap remains enforced at or below setpoint (mock).
- Evidence: EMS brief revB attached; configuration export available at closeout (Phase 7).

MOCK / EXAMPLE ONLY

# Utility Deficiency / Additional Information Required (Mock)

Issued: 2026-02-25 | Reference: UTIL-EV-2026-00831 (mock)  
EV Charging Site Project — Phase 6 Inputs (MOCK)

Status:	Incomplete / Additional Information Required
Reason:	EMS documentation insufficient for utility review (mock)
Request:	Clarify monitoring point and fail-safe cap behavior; provide EMS listing excerpt (mock)
Submission method:	Utility portal message (mock)

MOCK / EXAMPLE ONLY

NOTE: Mock deficiency notice; replace with actual portal letter/message export.

## P2.1 Load Calculation Summary (Mock)

Prepared: 2026-01-22 (v1.0) | Basis: Phase 1 evidence pointers (mock)  
EV Charging Site Project — Phase 2 Outputs (MOCK)

This summary captures the key results of the Phase 2 load calculation. Replace with an Engineer-of-Record signed calculation and jurisdiction-specific methodology where required.

**Inputs (by evidence pointer, mock):**

- Panel schedules: P1/Inputs/P1-I02\_PanelSchedules\_MDP\_and\_Subpanels\_2026-01-16.pdf
- EVSE cut sheet: P1/Inputs/P1-I04\_EVSE\_CutSheet\_ElectriCharge\_L2-7.6-G\_revA.pdf
- AHJ/code basis: P1/Inputs/P1-I05\_AHJ\_Electrical\_Permitting\_CodeBasis\_2026-01-17.pdf
- EMS brief: P2/Inputs/P2-W04\_EMS\_TechnicalBrief\_revB\_2026-01-21.pdf

**Key calculation results (mock):**

Parameter	Value
Ports	8
EVSE continuous current / port	32A
Continuous factor	125%
Design current / port	40A
Total unmanaged EV current	320A
Headroom basis (screening)	250A
Result	Unmanaged exceeds headroom by 70A → EMS required

NOTE: Mock summary only; final engineering must be stamped where required.

## P2.2 Architecture Decision Record (Mock)

Prepared: 2026-01-22 (v1.0) | Decision: Managed-load architecture  
EV Charging Site Project — Phase 2 Outputs (MOCK)

This record documents the selected EV electrical architecture based on the Phase 2 load calculation and Phase 1 site constraints. Replace with an Engineer-of-Record signed decision where required.

### Decision drivers (mock):

- Project constraint: avoid service upgrade unless unavoidable.
- Unmanaged EV load (320A) exceeds headroom basis (250A).
- Maintain 8-port scope without reducing EVSE count.
- Adopt listed EMS/load management to cap aggregate EV demand.

### Selected architecture (mock):

- New EV subpanel: EVSP-1, 400A bus (mock).
- Feeder OCPD: 350A, 3-pole (mock).
- Branch circuits: (8) 40A OCPD for EVSE-01..EVSE-08 (mock).
- EMS: cap aggregate EV demand to  $\leq 250A$  (setpoint documented on drawings).

### Downstream impacts (mock):

- P3.1 one-line must depict EMS and cap logic; include fail-safe note placeholder.
- P3.4 schedules must reflect EVSP-1 and branch circuit IDs.
- P6 utility package should include EMS brief and cap statement.

NOTE: Mock decision record; replace with signed EOR memo and attachments.

# EMS Technical Brief (revB) — Load Management for EVSE (Mock)

Vendor brief (mock) | Rev: B | Date: 2026-01-21  
EV Charging Site Project — Phase 2 Inputs (MOCK)

This document is a mock technical brief for a listed Energy Management System (EMS) used to cap aggregate EV charging demand. Replace with actual vendor documentation and listing evidence.

## Key capabilities (mock):

- Aggregate current cap setpoint (mock): 250A at EV feeder.
- Per-port load allocation across up to 16 ports (mock).
- Fail-safe behavior: on comms loss, enforce conservative cap (mock).
- Listed to applicable standards (mock listing placeholders).
- Provides configuration export for as-built documentation (Phase 7).

## Integration points (mock):

- Measures feeder current via CTs at EVSP-1 feeder (monitoring point).
- Controls EVSE output via network interface (OCPP) or hardwired control (mock).
- Setpoint documented on one-line and notes sheet (Phase 3).

# EMS Technical Brief (revB) — Configuration + Compliance Notes (Mock)

Appendix: configuration fields (mock)  
EV Charging Site Project — Phase 2 Inputs (MOCK)

**Configuration fields (mock):**

<b>Project ID:</b>	EV-PA-001 (mock)
<b>Cap setpoint:</b>	250A
<b>Monitoring point:</b>	EV feeder at MDP/EVSP-1
<b>Fail-safe mode:</b>	Cap enforced on fault
<b>Export format:</b>	PDF + JSON (mock)

MOCK / EXAMPLE ONLY

NOTE: This is a generated mock EMS brief for documentation realism only.

# EVSE Cut Sheet (Mock) — ElectriCharge L2-7.6-G (revA)

Installer/Vendor PDF (mock format) | Rev: A  
EV Charging Site Project — Phase 1 Inputs (MOCK)

## Key Electrical Ratings (mock)

Supply system:	208Y/120V, 3-phase (line-to-line load) (mock)
Nominal output power:	7.6 kW (nominal)
Continuous current:	32A
Recommended OCPD:	40A
Enclosure:	NEMA 3R (mock)
Communications:	OCPP 1.6J (mock)
Listing:	UL 2594 / UL 2231 (mock)

## Installation Notes (mock)

Branch circuit sizing shall comply with applicable NEC/CEC requirements for continuous loads. A 40A breaker is typical for 32A continuous output. Final breaker and conductor sizing per Engineer-of-Record.



# EVSE Cut Sheet (Mock) — Wiring/Dimensions (revA)

ElectriCharge — Product Data Sheet (mock)  
EV Charging Site Project — Phase 1 Inputs (MOCK)

## Wiring (mock excerpt)

Input: L1, L2, L3, G (no neutral required). Optional control wiring per network kit (mock).

(Mock wiring diagram placeholder)

## Dimensions (mock)

- Height: 18.5 in
- Width: 12.0 in
- Depth: 6.0 in
- Mounting: wall or pedestal (mock accessory)

NOTE: Generated mock cut sheet for documentation format realism only.

# EVSE Cut Sheet (Mock) — Labeling / Installation Checklist (revA)

Field-install notes (mock)

EV Charging Site Project — Phase 1 Inputs (MOCK)

This page summarizes common electrical-only installation considerations typically included in manufacturer documentation or installer checklists. Final requirements must follow the AHJ-adopted code basis and the EOR permit set.

## Labeling / placarding (mock):

- Circuit identification label at EVSE and at panel schedule.
- If an EMS/load management system is used, label the controlled system and setpoint.
- Mark EVSE as continuous load; confirm breaker sizing basis (125%).

## Electrical notes (mock):

- No neutral required for line-to-line EVSE supply (if configured as such).
- Provide equipment grounding conductor with branch circuit conductors.
- Verify maximum OCPD per manufacturer listing.
- Final conductor sizing per terminal temperature ratings and derating factors.

NOTE: This checklist is illustrative for mock documentation realism.

# Stamped Permit Drawings (Mock)

P4.1 | Stamp date: 2026-01-29 | Engineer-of-Record: Priya Shah, PE (mock)  
EV Charging Site Project — Phase 4 Outputs (MOCK)

## STAMP BLOCK (mock)

Priya Shah, PE (mock)  
CA PE ##### (mock)  
Date: 2026-01-29

This cover page is added to represent an EOR stamped set. The remainder of the set is the compiled P3.6 unstamped permit set (mock).

NOTE: This is not a real stamp. For mock documentation only.

MOCK / EXAMPLE ONLY

# Permit Drawing Set — Unstamped (Compiled) (Mock)

P3.6

EV Charging Site Project — Phase 3 Outputs (MOCK)

This file represents the compiled unstamped electrical permit drawing set assembled from P3.1–P3.5. In a real project this compilation is performed under document control with sheet indexing and QA logs.

## Included sheets (mock):

- P3.1\_OneLine\_Prelim\_Unstamped\_2026-01-26.pdf
- P3.2\_SitePlan\_EVSE\_Locations\_Prelim\_2026-01-26.pdf
- P3.3\_Conduit\_Trenching\_Details\_ElectricalImpacting\_2026-01-26.pdf
- P3.4\_PanelSchedules\_Updated\_MDP\_and\_EVSP\_2026-01-26.pdf
- P3.5\_ElectricalNotes\_CodeSheets\_2026-01-26.pdf


MOCK / EXAMPLE ONLY

NOTE: This compilation is a mock artifact; replace with real CAD/PDF exports and stamps.

E-001 — One-Line Diagram (Preliminary, Unstamped) (Mock)

P3.1  
EV Charging Site Project — Phase 3 Outputs (MOCK)

ONE-LINE DIAGRAM (mock)



NOTES (mock):


- 1. Existing service basis: 800A, 208Y/120V, 3Ø (verify in Phase 1 evidence).
- 2. EVSE loads treated as continuous; branch OCPD basis 40A per 32A continuous (mock).
- 3. EMS/load management shown to cap aggregate EV demand to ≤250A (mock basis).
- 4. Final conductor sizing, AIC, and coordination to be confirmed in stamped set.

<b>PROJECT (mock):</b> EV Charging Site Project	<b>SHEET:</b> E-001	<b>ISSUED FOR:</b>
<b>SHEET TITLE:</b> One-Line Diagram (Preliminary)	<b>REV:</b> 0	<b>UNSTAMPED</b>
<b>ADDRESS:</b> Place (Palo Alto, CA) (mock)	<b>DATE:</b> 2026-01-26	(electrical-only)

E-002 — Site Plan with EVSE Locations (Preliminary) (Mock)

P3.2  
EV Charging Site Project — Phase 3 Outputs (MOCK)

GARAGE PLAN — EVSE LOCATION OVERLAY (mock)



<b>PROJECT (mock):</b> EV Charging Site Project	<b>SHEET:</b> E-002	<b>ISSUED FOR:</b>
<b>SHEET TITLE:</b> Site Plan — EVSE Locations	<b>REV:</b> 0	UNSTAMPED
<b>ADDRESS:</b> Place (Palo Alto, CA) (mock)	<b>DATE:</b> 2026-01-26	(electrical-only)

# E-003 — Conduit & Trenching Details (Electrical-Impacting) (Mock)

P3.3  
EV Charging Site Project — Phase 3 Outputs (MOCK)

This sheet documents electrical-impacting routing assumptions, transition points, and typical details. It is not a civil/constructability plan.

DETAIL 1 — Feeder Path (mock)

MDP → EVSP-1 assumed path length: 165 ft (basis)

DETAIL 2 — Typical Raceway Notes (mock)

- Raceway sized per NEC/CEC Chapter 9 (mock).

- Parallel conductors permitted as designed (mock).

- Provide EGC with feeder conductors.

- Maintain separation from comms wiring (as applicable).

DETAIL 3 — EVSE Branch Typical (mock)

- Branch: 40A OCPD for 32A continuous (mock basis).

- Conductor sizing per terminal temp rating + derating.

- Provide disconnecting means as required by code/AHJ.

- Label EVSE circuit ID at equipment and panel.

DETAIL 4 — Grounding/Bonding Intent (mock)

- Bond raceways where required (mock).

- EGC sized per code basis (final by EOR).

- Panel ground bars bonded to GES (reference).

- Provide bonding jumpers at transitions.

<div>PROJECT (mock): EV Charging Site Project</div> <div>SHEET TITLE: Conduit &amp; Trenching Details (Electrical-</div> <div>ADDRESS: Place (Palo Alto, CA) (mock)</div>	<div>SHEET: E-003</div> <div>REV: 0</div> <div>DATE: 2026-01-26</div>	<div>ISSUED FOR:</div> <div>UNSTAMPED</div> <div>(electrical-only)</div>
---	---	--

File: P3.3\_Conduit\_Trenching\_Details\_ElectricalImpacting\_2026-01-26.pdf | Generated: 2026-01-22 | Page 1

# E-004 — Updated Panel Schedules (MDP + EVSP-1) (Mock)

P3.4  
EV Charging Site Project — Phase 3 Outputs (MOCK)

## MDP — Updated (excerpt) (mock)

Slot	Breaker	Load	Notes
40/42/44	350A 3P	EVSP-1 feeder	Managed to 250A (mock)
17	200A 3P	SUBP-1	Existing
57	Spare	Spare/Space	Available 3-pole

## EVSP-1 — New (excerpt) (mock)

Slot	Breaker	Load	Notes
1	40A 3P	EVSE-01	32A cont (mock)
2	40A 3P	EVSE-02	32A cont (mock)
3	40A 3P	EVSE-03	32A cont (mock)
4	40A 3P	EVSE-04	32A cont (mock)
5	40A 3P	EVSE-05	32A cont (mock)
6	40A 3P	EVSE-06	32A cont (mock)
7	40A 3P	EVSE-07	32A cont (mock)
8	40A 3P	EVSE-08	32A cont (mock)

NOTE: schedules are mock excerpts; full schedules included per P1 evidence in real project.

<b>PROJECT (mock):</b> EV Charging Site Project	<b>SHEET:</b> E-004	<b>ISSUED FOR:</b>
<b>SHEET TITLE:</b> Panel Schedules (MDP + EVSP-1)	<b>REV:</b> 0	UNSTAMPED
<b>ADDRESS:</b> Place (Palo Alto, CA) (mock)	<b>DATE:</b> 2026-01-26	(electrical-only)





# E-005 — Electrical Notes & Code Sheet (Mock)

P3.5  
EV Charging Site Project — Phase 3 Outputs (MOCK)

## GENERAL NOTES (electrical-only, mock)

- 1. Applicable code basis: 2022 California Electrical Code (CEC) (mock). Verify AHJ amendments.
- 2. EVSE loads treated as continuous; size OCPD and conductors accordingly (125% basis).
- 3. EMS/load management (if used) shall be listed and configured to enforce aggregate cap (mock: 250A).
- 4. Provide identification labeling for EV equipment and circuits; coordinate with panel schedules.
- 5. Provide grounding and bonding per code; bond raceways as required.
- 6. Verify available fault current and minimum AIC ratings in final stamped set.

## SYMBOLS / LEGEND (mock)

-  EVSE location marker
-  EMS / Load management annotation

<b>PROJECT (mock):</b> EV Charging Site Project	<b>SHEET:</b> E-005	<b>ISSUED FOR:</b>
<b>SHEET TITLE:</b> Electrical Notes & Code Sheet	<b>REV:</b> 0	UNSTAMPED
<b>ADDRESS:</b> Place (Palo Alto, CA) (mock)	<b>DATE:</b> 2026-01-26	(electrical-only)